

TOWN OF LUNENBURG

TOL2026018

ADDENDUM #1

1. The tender submission says it is to be hand delivered. In the past, we have been able to submit this via email (It was an email submission on Phase 1). Are we able to submit our tender via email?

Yes, email is acceptable.

2. Closing date of tender will be now Friday August 21, 2:00pm

3. Will we be able to shut down this section of road and put up a detour around during construction?

It is the responsibility of the Contractor to propose the traffic management measures to execute the work to the Town's satisfaction. We are prepared to consider a detour to facilitate the work, provided details such as routing, the approach to access of properties within the work zone are adequately addressed, etc. are sufficiently covered

4. Note 1 for detail 1 on drawing C-001 indicates any areas of unsuitable material will need to be replaced with surge rock and/or geogrid. There are no provisional pay items for this work. Please provide provisional pay items for this work or confirm there will be no over excavation of unsuitable material and replacement with surge? If provisional items are provided, please indicate if the replacement is with geogrid or surge rock or both?

We don't anticipate that unsuitable material will be encountered as the road has not been failing, so this detail note could be deleted.

5. The curb detail on drawing C-001 shows what looks like two runs of rebar. It is hard to tell as these aren't labeled. This would be atypical for new curb, and these were deleted in phase 1. Please confirm that rebar isn't required for this phase? If they are required, please indicate the size of the new rebar?

This rebar can be removed.